

NEW ASHTON ARCH

Presented by **AECOM SA**
June 2021

WESTERN CAPE GOVERNMENT



BACKGROUND
DESIGN AND CONSTRUCTION CONSIDERATIONS
CONSTRUCTION OF TEMPORARY AND PERMANENT WORKS
CONSTRUCTION CHALLENGES
TRANSVERSE LAUNCHING
ACKNOWLEDGEMENTS



WESTERN CAPE GOVERNMENT

AECOM Imagine it.
Delivered.



WESTERN CAPE GOVERNMENT

AECOM Imagine it.
Delivered.

BACKGROUND

WESTERN CAPE GOVERNMENT

AECOM Imagine it.
Delivered.

Strategic road link

- Important local and national route
- Main link between Ashton and Montagu
- Important Tourism Route
- Scenic and historic considerations



Flooding

Various floods in the area leading to damage and related road closures leading to geometric, pavement and structural improvements:

- To enhance flood resistance
- Improve flood capacity at critical locations



Why upgrade Route R60/62?

Flooding

- Hydraulically inefficient
- Recurring floods resulting in damages
- Debris build-up



Why upgrade Ashton Bridge?





Overtopping of existing bridge



Debris build-up



Damage and debris build-up

Hydraulic Capacity


- Arched deck soffit hydraulically inefficient
- Pier in river obstructs flow and allows for debris build-up
- Overtops during large floods event



Why upgrade Ashton Bridge?

Existing Bridge Configuration

- On R60 which is an important link between N1 and N2
- Built in 1930 and widened in 1950
- Negative impact on traffic flow



Existing Bridge Configuration

- Built in 1930's [single lane]
- Substantially widened in 1950 [(x2) 3,35m lanes + 1,80m sidewalks]
- Total Length of bridge \pm 95m
- Angle of Skew 50°
- Road level varies between 5m to 8m above NGL

Option 1, 2 & 4: Voided Slab or Precast Beams


- Deck depth = approx. 1,50m
- Raise existing FRL with 3,00m to achieve min freeboard
- 4 Piers in river = debris build-up
- Higher approach fills complicates intersections



EDGE - B2644
 POINT OF INTERSECTION
 AREA VALUE: 17 757,000
 AREA OF SKEW: 49°48'34"
 CO-ORDINATES:
 Y = 87 012,579
 X = 3 745 615,428
 FRL = 165,511

Option 3: Tied Arch Bridge

- Deck depth = 1,00m
- Raise existing FRL with 2,50m to achieve min freeboard
- No piers in river = no debris build-up



MONTAGU →


Options considered

| Key Design Considerations | Voided Slab Deck with Temporary Bypass | Voided Slab Deck built in Half Widths | Single span Tied Arch Launched transversely | a) Precast Beams b) Temp Bypass Half widths |
|---|--|---------------------------------------|---|--|
| Hydraulic efficiency | ✓ | ✓ | ✓✓ | ✓, ✓ |
| Construction flood risk | ✗ | ✓ | ✓ | ✗, ✗ |
| Geometric Alignment | ✓ | ✗ | ✓✓ | ✓, ✓ |
| Traffic Accommodation | ✓✓ | ✗ | ✓✓ | ✓✓, ✗ |
| Aesthetics | ✓ | ✓ | ✓✓ | ✗, ✗ |
| Constructability | ✓✓ | ✗ | ✓ | ✓, ✗ |
| Ratio: Construction costs | 1.15 | 1.0 | 1.35 | 1.20 |
| Ratio: Construction + indirect costs | 1.20 | 1.0 | 1.10 | 1.25 |

Final Concrete Tied Arch Configuration




General details of Ashton Arch



Transverse Launching Concept

TEMPORARY WORKS CONCEPT (TENDER STAGE)



DESIGN & CONSTRUCTION CONSIDERATIONS

WESTERN CAPE GOVERNMENT

AECOM Imagine it.
Delivered.

Structural form and bridge aesthetics

- Attention was paid to the historical significance of existing multiple-span arch bridge
- Major benefit of the arch is ability to span over the entire river and consequently improves the hydraulic efficiency, specifically due to the large skew angle
- A tied-arch bridge is particularly suitable for this topographic location, since it suspends the roadway and does not require propped arch founding conditions
- V-hanger-configuration was adopted in preference to the vertical hanger orientation, since it provides an aesthetic advantage
- Aesthetically, the slender tied arch design is appropriate since the depth of the proposed roadway above the riverbed with a visually appealing light deck.
- The tied-arch form expresses a visualisation of flowing of forces with light hangers and slender members displaying a transparency accentuated by the surrounding mountains

Concrete as the primary construction material

- Primary load transfer mechanism of the arch rib is compression
- Due to the complex nature of the flow of forces within the spring point, particular attention to modelling and analysing this element was paid during the detail design
- In terms of concrete volumes cast, the four spring points are massive elements, requiring management of thermal performance (heat of hydration) of the concrete and associated cumulative strains
- Particular concrete placement methodology was adopted to exercise due care in the construction of the tie points, using pre-inserted temporary steel tubes (160mm dia)
- A specially developed, high mobility 50/13 pumpable, concrete mix was designed for casting the tie points.
- Thermal performance was predicted according to Ciria C660 'Early-age thermal cracking control of concrete.
- Additionally, the peak temperature within these massive elements were monitored via embedded Giatec SmartRock sensors

Concrete as the primary construction material



Steel tube concrete pour access provided through congested reinforcement



Top/inclined shutters introduced incrementally as pour progressed (temporary inspection holes visible)

Structural modelling for design and construction

- Structure was modelled locally using Bentley's RM Bridge and internal design review conducted by the AECOM's UK complex bridge specialist team using SOFISTIK
- The state-of-the-art analysis software packages modelled construction stage and in-service analysis for design.
- Models were updated with concrete material parameters, determined from laboratory testing allowing accurate simulation of stage & time-dependant material behaviour
- Updated models were calibrated for determination of the following with continuous backward analysis comparisons of actual results during construction:
 - Hanger length determination,
 - Hanger force distribution optimisation,
 - Pre-camber requirements & influence of temporary works displacements,
 - Movement capacities of (temporary and permanent) & expansion joints

CONSTRUCTION OF TEMPORARY AND PERMANENT WORKS

WESTERN CAPE GOVERNMENT

AECOM Imagine it.
Delivered.

Temporary Works

- Temporary abutment
- Caisson foundations
- Temporary Columns
- Lateral support



Temporary works



Deck False Work

- Transverse steel girders
- Sand jacks
- Longitudinal steel girders



Deck False Work

- Soffit formwork
- Arch spring point



Structural Displacements

- Foundations
- Temporary works & falsework
- Permanent works during all construction stages & service life




Arch rib segmental construction



compression
 $\sigma/\sigma_{fc} = -27738.148$

0.0

tension
 $\sigma/\sigma_{fc} = 27738.148$



Cast beams and alternate slabs

Prestress Longitudinal beams
Prestress Transverse beams

1 Jul 1 Aug 1 Sep

Complete Arch and strip falsework

Creep and Shrinkage for 108 days

1 Oct 1 Nov 1 Dec 1 Jan

STG 2 Hanger Stressing

STG 1 Hanger Stressing

1 Feb 1 Mar

Creep and Shrinkage for 25 days

C&S 81 days

Release Deck staging

Creep and Shrinkage for 70 days

1 Apr 1 May 1 Jun 1 Jul 1 Aug

Apply Permanent ADL

Bridge onto permanent bearings

Creep and Shrinkage for 143 days

1 Sep 1 Oct 1 Nov 1 Dec 1 Jan 1 Feb


C&S 24 d

C&S 365d

C&S 730d

C&S 10 000 days

Horizontal Deck Movement



Completion of hit and miss construction
Stress longitudinal beams

Before installing hangers

After hanger installation

Temporary bearing movement range

Install perm bearings

ADL added

30 years C&S

Final C&S

Permanent bearing movement range

Stay Cable Lengths

- Unintentional variations (construction tolerances & modelling)
- Intentional variations (Time dependent material behaviour)
- Available fork socket tolerances

| STAY CABLE NUMBER | | Tolerance allowances (+ increase distance : - reduces distance) | | | | | | | | | | | | | | | TOTAL CONTROL SHORTENING OF THEORETICAL CHORD DISTANCE |
|-------------------|----------|---|----------------|-----------------------------|--------------------------|-------------|------------------|---------------------|------------------------------------|--|-----------------|-------------------------------|--------------------------------------|-----------------|------------------|----------------------------------|--|
| | | Unintentional variation (extreme + or - indicated) | | | | | | | | Intentional variations (actual + or - indicated) | | | | | | | |
| | | Temporary works | Concrete works | Cast Anchors & fixing bolts | Cable Length manufacture | Fork socket | Structural model | Material properties | Total unintentional chord variance | Arch Deflection (After formwork removal) | Arch temp range | Cable temp range (20 deg var) | Arch Deflection (Cable Installation) | Deck deflection | Cable Elongation | Total Intentional chord variance | |
| NORTH | SOUTH | (mm) | (mm) | (mm) | (mm) | (mm) | (mm) | (mm) | (mm) | (mm) | (mm) | (mm) | (mm) | (mm) | (mm) | (mm) | |
| N1, N24 | S1, S24 | -2 | -1 | -10 | -10 | -5 | -1 | -1 | -30 | 0 | 0 | 0 | -4 | -2 | -7.37 | -12 | -42 |
| N2, N23 | S2, S23 | -4 | -2 | -10 | -10 | -5 | -2 | -1 | -35 | 0 | 0 | 0 | -7 | -2 | -7.74 | -16 | -51 |
| N3, N22 | S3, S22 | -4 | -2 | -10 | -10 | -5 | -2 | -1 | -35 | 0 | 0 | 0 | -7 | -4 | -15.18 | -26 | -61 |
| N4, N21 | S4, S21 | -12 | -6 | -10 | -10 | -5 | -5 | -4 | -52 | 0 | 0 | 0 | -20 | -4 | -13.01 | -37 | -88 |
| N5, N20 | S5, S20 | -12 | -6 | -10 | -10 | -5 | -5 | -4 | -52 | 0 | 0 | 0 | -20 | -6 | -20.61 | -47 | -98 |
| N6, N19 | S6, S19 | -26 | -13 | -10 | -10 | -5 | -11 | -9 | -83 | 0 | 0 | 0 | -43 | -6 | -14.68 | -64 | -147 |
| N7, N18 | S7, S18 | -26 | -13 | -10 | -10 | -5 | -11 | -9 | -83 | 0 | 0 | 0 | -43 | -9 | -27.13 | -79 | -162 |
| N8, N17 | S8, S17 | -41 | -21 | -10 | -10 | -5 | -17 | -14 | -117 | 0 | 0 | 0 | -68 | -9 | -6.92 | -84 | -201 |
| N9, N16 | S9, S16 | -41 | -21 | -10 | -10 | -5 | -17 | -14 | -117 | 0 | 0 | 0 | -68 | -10 | -31.92 | -111 | -228 |
| N10, N15 | S10, S15 | -54 | -27 | -10 | -10 | -5 | -23 | -18 | -147 | 0 | 0 | 0 | -90 | -10 | -26.19 | -126 | -273 |
| N11, N14 | S11, S14 | -54 | -27 | -10 | -10 | -5 | -23 | -18 | -147 | 0 | 0 | 0 | -90 | -11 | -37.30 | -138 | -285 |
| N12, N13 | S12, S13 | -57 | -29 | -10 | -10 | -5 | -24 | -19 | -154 | 0 | 0 | 0 | -95 | -11 | -12.76 | -119 | -273 |

CONSTRUCTION CHALLENGES

WESTERN CAPE GOVERNMENT

AECOM Imagine it.
Delivered.

Original Construction Contract Termination

WESTERN CAPE GOVERNMENT

AECOM Imagine it.
Delivered.

Original Construction Contract termination & New Contracts

- Original Construction Contract was awarded to Basil Read Construction (BR) and commenced during 2015
- Contract was terminated during 2018 after BR was placed under business rescue
- H&I Construction was awarded an Interim Maintenance Contract to facilitate essential works and maintain traffic and safety measures.
- H&I Construction was also successful with the New Construction Contract which commenced during 2019
- Engineer and client appointed temporary works designer managed certain works during Interim Maintenance Contract & exercised control over free issue items eg. Post Tension installation, hanger anchors, falsework for arch etc.

Post tensioning

WESTERN CAPE GOVERNMENT

AECOM Imagine it.
Delivered.

Post Tensioning

- Strand property verification
- Strand installation method & lubrication
- Duct condition verification ; Friction & Wobble calibration
- Lift off testing





Figure 40 Elongation comparison

Post tensioning



Post tensioning



Post tensioning



Post tensioning






Figure 47 Wobble coefficient calibration (Leonhardt, 1964)

DUCT 3,4,9,10
Wobble "k" Sensitivity Analysis ($\mu = 0.30$)



DUCT 5,6,11,12
Wobble "k" Sensitivity Analysis ($\mu = 0.30$)



Post tensioning



Figure 49 Jack with magnetic precision Dial Gauge

- T3
- T9
- T4
- T10




Figure 57 Typical lift off test results

Hanger anchors manufacturing

WESTERN CAPE GOVERNMENT

AECOM Imagine it.
Delivered.

Hanger anchor manufacturing


- Rejection of original cast iron hangers
- Procurement & Manufacturing (International)
- QCP & Authorized Inspection Authority (OHS requirements)
- Compatibility & service life verifications (dimensional, fatigue, inspection & maintenance manuals)
- Important service life considerations
 - The structural form dictates that the anchors are subject to the following general loading regime:
 - A free tensile load in which (in a failure situation) a significant proportion of the load would still be applied up to rupture
 - Limited redundancy with potential susceptibility to “unzipping” failure
 - The form of the anchor connection results in a partial creation of a hidden critical element (the embedded section), that means subsequent complete inspection will be difficult.

Hanger anchor manufacturing

- Rejection of original cast iron hangers due to inadequate durability and fatigue resistance parameters
- Procurement & Manufacturing (International) resulted in new compound steel plate solutions in view of programming constraints
- Compatibility & service life verifications (dimensional, fatigue, inspection & maintenance manuals) with important service life considerations
- The structural form dictates that the anchors are subject to the following general loading regime:
 - A free tensile load in which (in a failure situation) a significant proportion of the load would still be applied up to rupture
 - Limited redundancy with potential susceptibility to “unzipping” failure
- The form of the anchor connection results in a partial creation of a hidden critical element (the embedded section), that means subsequent complete inspection will be difficult

Hanger anchor manufacturing

| AECOM-SA-approaches | | | | AECOM-UK-Ltd |
|---|--|--|--|---|
| Scenario-description | Impact-on-programme | Actions | Risks | REVIEW-COMMENT |
| Scenario A: Acceptance in current condition based on a Fit for Service (FFS) analysis | Only scenario that would allow pre-arch casting installation | AECOM-UK specialists to advise on probability of successful outcome based on available information | Negative FFS result, uncertain long-term effect on structural system | Unlikely to be sufficient considering the variability of defects and number of components. Even if metallurgical FFS recommendation is positive it will be difficult to align with structural design responsibility for a new 120-year lifespan public CC3 structure. |
| Scenario B: Re-heat treatment of all anchor plate | Process would require post-arch casting installation | Assess effects of re-heat treatment and property improvement probability | This may provide the least duration risk, metallurgical view not too positive with current casting material composition | Metallurgical specialist advice appears to doubt this route but has to be discussed in detail. Substantial upgrade of Charpy and %elongation results required to meet the spec are difficult to achieve, particularly when considering the large number of potentially affected cast components. Post-arch casting installation would require careful consideration to avoid incorporation of a defect. |
| Scenario C: Remanufacture of all components | Process would require post-arch casting installation | Steel castings or steel plate manufacturing options to be considered with costs, sourcing internationally & delivery | Indications are that a minimum 6-month procurement process required, any delays could significantly impact on construction | This is the structurally safe option based on the currently available and presented information. Efforts to minimise the cost and programme implications could be made but are nevertheless likely to be significant. Post-arch casting installation would require careful consideration to avoid incorporation of a defect. |
| Scenario D: Strengthening of all components | Process would require post-arch casting installation | Ultra-high strength steel plate strengthening options to be considered with feasibility, cost etc. | Feasibility uncertain but may be easier than remanufacturing with reduced cost implication | Based on the nature of the defects, the number and shape of the cast components <u>this option</u> is not considered feasible. Welding high strength plates to this type of high yield casting would be problematic and could potentially make matters worse. |



Welding operations





Welding operations







Machining operations



Heat treatment and quality control





Galvanizing trials



Thermal Metal Spray and paint coating

Coating System :


- TMS (Zinc , 125 micron)
- Carboguard 635 (150 micron)
- Carbothane 137 HS (90 micron)




Hanger Anchor Installation

WESTERN CAPE GOVERNMENT

AECOM Imagine it.
Delivered.







Installation testing

| | Average | | | Average | | | Average | | | Average | | | Average | |
|----------------------|-----------------------|--|--------|-----------------------|--|------------------|-----------------------|--|--------|-----------------------|--|--------|-----------------------|--|
| Avg N | 258.3248 | | Avg N | 255.83 | | Avg N | 255.65 | | Avg N | 258.51 | | Avg N | 260.31 | |
| Avg S | 260.04082 | | Avg S | 259.03 | | Avg S | 258.92 | | Avg S | 260.81 | | Avg S | 259.79 | |
| Avg W | 259.03176 | | Avg W | 256.97 | | Avg W | 256.98 | | Avg W | 258.71 | | Avg W | 259.24 | |
| Avg E | 259.33324 | | Avg E | 257.88 | | Avg E | 257.59 | | Avg E | 260.6 | | Avg E | 260.86 | |
| diff | | Worst Case | diff | | Worst Case | diff | | Worst Case | diff | | Worst Case | diff | | Worst Case |
| W to E | 0.3014872 | 1.7166 | W to E | 0.902 | 3.1995 | W to E | 0.6127 | 3.2676 | W to E | 1.8891 | 2.2975 | W to E | 1.612 | 1.612 |
| N to S | 1.7166313 | | N to S | 3.1995 | | N to S | 3.2676 | | N to S | 2.2975 | | N to S | 0.5168 | |
| | | | | | | | | | | | | | | |
| | Bolt 1 | | | Bolt2 | | | Bolt3 | | | Bolt4 | | | Bolt 5 | |
| | Measuring plate color | Washer plate extrapolated error standard | | Measuring plate color | Washer plate extrapolated error standard | | Measuring plate color | Washer plate extrapolated error standard | | Measuring plate color | Washer plate extrapolated error standard | | Measuring plate color | Washer plate extrapolated error standard |
| NW | 258.35 | 258.16 | NW | 256.29 | 255.45 | NW | 256.23 | 255.44 | NW | 258.23 | 257.37 | NW | 259.38 | 259.28 |
| SE | 259.99 | 260.18 | SE | 258.7 | 259.55 | SE | 258.51 | 259.32 | SE | 260.69 | 261.56 | SE | 260.27 | 260.37 |
| NE | 258.62 | 258.49 | NE | 256.67 | 256.2 | NE | 256.41 | 255.87 | NE | 259.73 | 259.65 | NE | 261.14 | 261.34 |
| SW | 259.77 | 259.9 | SW | 258.02 | 258.5 | SW | 257.97 | 258.52 | SW | 259.97 | 260.05 | SW | 259.41 | 259.21 |
| | | | | | | | | | | | | | | |
| Measured: 27/05/2020 | | | | | | | | | | | | | | |
| 258.16 | 258.49 | | 255.45 | 256.2 | | 255.44 | 255.87 | | 257.37 | 259.65 | | 259.28 | 261.34 | |
| 259.9 | 260.18 | | 258.5 | 259.55 | | 258.52 | 259.32 | | 260.05 | 261.56 | | 259.21 | 260.37 | |
| | | | | | | | | | | | | | | |
| | | | | | | Anchor N2 | | | | | | | | |
| 262.64 | 260.93 | | 2614 | 262.15 | | 258.19 | 258.68 | | 259.99 | 259.22 | | 258.79 | 259.34 | |
| 259.35 | 258.34 | | 258.53 | 259 | | 255.35 | 256.28 | | 256.1 | 254.71 | | 256.75 | 257.54 | |
| | | | | | | | | | | | | | | |
| | Bolt 10 | | | Bolt 9 | | | Bolt8 | | | Bolt7 | | | Bolt 6 | |
| | Measuring plate color | Washer plate extrapolated error standard | | Measuring plate color | Washer plate extrapolated error standard | | Measuring plate color | Washer plate extrapolated error standard | | Measuring plate color | Washer plate extrapolated error standard | | Measuring plate color | Washer plate extrapolated error standard |
| NW | 262.24 | 262.64 | NW | 260.91 | 261.4 | NW | 257.8 | 258.19 | NW | 258.91 | 259.99 | NW | 258.67 | 258.79 |
| SE | 258.74 | 258.34 | SE | 259.5 | 259 | SE | 256.68 | 256.28 | SE | 255.81 | 254.71 | SE | 257.66 | 257.54 |
| NE | 260.78 | 260.93 | NE | 261.41 | 262.15 | NE | 258 | 258.68 | NE | 258.58 | 259.22 | NE | 259.1 | 259.34 |
| SW | 259.5 | 259.35 | SW | 259.28 | 258.53 | SW | 256.04 | 255.35 | SW | 256.75 | 256.1 | SW | 256.99 | 256.75 |
| | | | | | | | | | | | | | | |
| | Average | | | Average | | | Average | | | Average | | | Average | |
| Avg N | 261.78552 | | Avg N | 261.78 | | Avg N | 258.44 | | Avg N | 259.6 | | Avg N | 259.06 | |
| Avg S | 258.84448 | | Avg S | 258.76 | | Avg S | 255.81 | | Avg S | 255.41 | | Avg S | 257.15 | |
| Avg W | 260.99796 | | Avg W | 259.96 | | Avg W | 256.77 | | Avg W | 258.05 | | Avg W | 257.77 | |
| Avg E | 259.63204 | | Avg E | 260.58 | | Avg E | 257.48 | | Avg E | 256.96 | | Avg E | 258.44 | |
| diff | | Worst Case | diff | | Worst Case | diff | | Worst Case | diff | | Worst Case | diff | | Worst Case |
| W to E | 1.3659217 | 2.941 | W to E | 0.8127 | 3.0123 | W to E | 0.7148 | 2.6209 | W to E | 1.0807 | 4.1951 | W to E | 0.6768 | 1.9197 |
| N to S | 2.9410386 | | N to S | 3.0123 | | N to S | 2.6209 | | N to S | 4.1951 | | N to S | 1.9197 | |






Washer plate machining



Arch Anchor plates



- 2 or more tensioning cycles result less anchorage losses according to Macalloy bar literature
- 3 stressing cycles on Arch anchor plates.

Tie Beam Anchor plates



- Bars shorter than the Arch ones.
- 4 stressing cycles



Anchor plate tensioning summary

- 484 bars tensioned
- Over 1200 lift-off tests
- Over 1900 washer plate alignment measurements
- 2400 litres of grout


Hanger Installation

WESTERN CAPE GOVERNMENT

AECOM Imagine it.
Delivered.



Utilisation of the C-hook



Utilisation of the C-hook




Hanger Tensioning

WESTERN CAPE GOVERNMENT

AECOM Imagine it.
Delivered.

Hanger tensioning sequence





Stage 1 = 50% of load -> Stage 2 = 100% load

The intent of this process was to start by removing the slack from the cables and to get some stiffness into the structural system before the cables are sequentially stressed to their design force



Simultaneous tensioning of 2 cables per Arch

Live structural monitoring during tensioning



Tensioning checks and calculations



Instrumentation and Monitoring

WESTERN CAPE GOVERNMENT

AECOM Imagine it.
Delivered.

FEM Model Review and Calibration

Bentley RM Bridge Advanced V8

AECOM SA design

30 Construction Stages

Rigid support for deck falsework

Spring point modeled with rigid links

C&S models – BS 5400

Sofistik 2014


AECOM UK

89 Construction Stages


Calculated stiffness for deck falsework

Springing point modeled with shell elements




C&S models – TMH 7




TIED ARCH BRIDGE DESIGN MODEL



Strain Monitoring



Strain Monitoring



Strain Monitoring

The screenshot displays the LabVIEW SignalExpress software interface for strain monitoring. The main window is titled "D:\ashton_pm.zproj - LabVIEW SignalExpress". The interface includes a menu bar (File, Edit, View, Tools, Add Step, Operate, Window, Data View, Help) and a toolbar with icons for "Add Step", "Stop", "Run Once", "Record", "Reset All", and "Error List".

The left sidebar contains several panels:

- Monitor / Record**: Shows the current state as "Running".
- DAQmx Acquire**: Includes "Analog Input" and "Strain" options.
- Subset and Resample**: Includes "Strain" and "subset signal 1" options.
- Save to ASCII/LVM**: Lists various subset signals such as "subs...cDAQ2Mod1_ai0 1", "subset...cDAQ2Mod1_ai1", "subset...cDAQ2Mod1_ai2", "subset...cDAQ2Mod1_ai3", "subset...cDAQ2Mod2_ai0", "subset...cDAQ2Mod2_ai1", "subset...cDAQ2Mod2_ai2", and "subset...cDAQ2Mod2_ai3".
- Logs** and **Snapshots**: Empty panels for logging and snapshots.


The main display area contains two plots:

- Display 1**: A plot of "Strain (strain)" vs "Time (s)". The y-axis ranges from -12u to 26u, and the x-axis ranges from 0 to 1.9995. Multiple colored traces (blue, purple, red, yellow, green) show high-frequency noise around a baseline.
- Display 2**: A plot of "Voltage (V)" vs "Time (s)". The y-axis ranges from -10u to 24u, and the x-axis ranges from 0 to 1.8. Multiple colored traces show low-frequency oscillations around a baseline.

A legend on the right side of the interface lists the data series:

- Strain
 - cDAQ2Mod1_ai0 (strain)
 - cDAQ2Mod1_ai1 (strain)
 - cDAQ2Mod1_ai2 (strain)
 - cDAQ2Mod1_ai3 (strain)
 - cDAQ2Mod2_ai0 (strain)
 - cDAQ2Mod2_ai1 (strain)
 - cDAQ2Mod2_ai2 (strain)
 - cDAQ2Mod2_ai3 (strain)
- subset signal 1
 - cDAQ2Mod1_ai0 1
 - cDAQ2Mod1_ai1
 - cDAQ2Mod1_ai2
 - cDAQ2Mod1_ai3
 - cDAQ2Mod2_ai0
 - cDAQ2Mod2_ai1
 - cDAQ2Mod2_ai2
 - cDAQ2Mod2_ai3


A TeamViewer overlay is visible in the bottom right corner, showing the session name "Henrich (1 304 191 172)" and the date "2020/07/20".



Displacement monitoring



Cable Tension Measurement




| Cables | | Stage 1 Cable Installation | | | | | | | | | | | Stage 2 Cable Installation | | | | | | | | | | | | |
|--------|----|----------------------------|---------------|---------------|---------------|---------------|---------------|---------------|---------------|---------------|---------------|---------------|----------------------------|----------------|----------------|----------------|----------------|----------------|----------------|----------------|----------------|----------------|----------------|----------------|----------------|
| | | 4101 STG4H | 4102 STG4J | 4103 DTG4L | 4104 STG4G | 4105 STG4I | 4106 STG4K | 4107 STG4A | 4108 STG4B | 4109 STG4C | 4110 STG4D | 4111 STG4E | 4112 STG4F | 4121 STG4HH | 4122 STG4JJ | 4123 DTG4LL | 4124 STG4GG | 4125 STG4II | 4126 STG4KK | 4127 STG4AA | 4128 STG4BB | 4129 STG4CC | 4130 STG4DD | 4131 STG4EE | 4132 STG4FF |
| N | 4 | 650 | 682 | 886 | 850 | 758 | 845 | 820 | 718 | 587 | 472 | 442 | 445 | 1089 | 1055 | 1043 | 986 | 828 | 813 | 797 | 730 | 631 | 565 | 571 | 599 |
| N | 8 | | 930 | 684 | 687 | 600 | 399 | 420 | 472 | 493 | 393 | 190 | 44 | 0 | 1092 | 961 | 956 | 828 | 626 | 627 | 623 | 582 | 436 | 267 | 183 |
| N | 12 | | | 793 | 810 | 827 | 434 | 456 | 531 | 626 | 669 | 576 | 249 | 178 | 100 | 1200 | 1198 | 1182 | 870 | 872 | 885 | 919 | 964 | 839 | 388 |
| N | 2 | | | | 466 | 429 | 472 | 414 | 323 | 257 | 211 | 194 | 184 | 81 | 63 | 51 | 688 | 643 | 637 | 612 | 569 | 534 | 522 | 536 | 549 |
| N | 6 | | | | | 825 | 809 | 819 | 821 | 735 | 561 | 450 | 421 | 282 | 186 | 155 | 137 | 988 | 919 | 916 | 887 | 783 | 631 | 569 | 584 |
| N | 10 | | | | | | 1019 | 1042 | 1114 | 1193 | 1198 | 1030 | 749 | 664 | 552 | 189 | 186 | 151 | 1317 | 1318 | 1324 | 1330 | 1293 | 1115 | 831 |
| N | 1 | | | | | | | 867 | 693 | 666 | 696 | 756 | 806 | 744 | 788 | 818 | 739 | 716 | 741 | 1131 | 1035 | 994 | 1002 | 1014 | 1021 |
| N | 3 | | | | | | | | 913 | 766 | 762 | 856 | 963 | 817 | 888 | 966 | 906 | 813 | 869 | 827 | 1217 | 1078 | 1038 | 1034 | 1051 |
| N | 5 | | | | | | | | | 962 | 842 | 868 | 976 | 806 | 831 | 938 | 909 | 729 | 780 | 769 | 696 | 1215 | 1054 | 975 | 985 |
| N | 7 | | | | | | | | | | 1115 | 999 | 1024 | 877 | 785 | 862 | 852 | 702 | 676 | 677 | 665 | 571 | 1335 | 1105 | 1040 |
| N | 9 | | | | | | | | | | | 1213 | 1087 | 975 | 811 | 729 | 723 | 653 | 485 | 488 | 498 | 493 | 391 | 1375 | 1118 |
| N | 11 | | | | | | | | | | | | 1208 | 1119 | 1003 | 623 | 620 | 590 | 313 | 316 | 333 | 367 | 396 | 190 | 1234 |

Cable Tension Measurement




$$T = 4f^2Lm$$



Cable tension Measurement

| Cable number | Measured first natural frequency (Hz) | Measured force (kN) | Targed force (kN) | % difference |
|--------------|---------------------------------------|---------------------|-------------------|--------------|
| 5 | 6.96 | 944 | 938 | 0.64% |
| 7 | 5.32 | 859 | 862 | -0.35% |
| 8 | 5.14 | 994 | 961 | 3.43% |
| 9 | 4.39 | 711 | 729 | -2.47% |
| 11 | 3.68 | 612 | 623 | -1.77% |
| 12 | 5.18 | 1214 | 1200 | 1.17% |



$$T = 4f^2Lm$$

Adverse founding conditions

WESTERN CAPE GOVERNMENT

AECOM Imagine it.
Delivered.

Adverse founding conditions at west abutment

- Significant amount of ground water
- comprehensive re-assessment
- 5 design scenarios were tested in the market to assess the cost and programme aspects.
- A large diameter (>1000mm) piling solution with approximate 10m length was adopted



TRANSVERSE LAUNCHING


WESTERN CAPE GOVERNMENT

AECOM Imagine it.
Delivered.

Transverse Launching

The proposed launching system consists of the following main components:


- 4 x 322 ton (VSL SLU 330) launching strand jacks plus 1 spare, including power pack and control unit;
- 4 x pulling cables, consisting of 31 strands each (15.3 mm dia, 276.7 kN UTS / strand);
- For additional pulling capacity - 2 x 120 ton (VSL SLU 120) cylinders which will be adapted by VSL to act as hollow plunger cylinders with necessary pipes to connect to main power pack and control unit.
- For additional pulling capacity - 50 mm diameter stress bar between hollow plunger cylinders and steel brackets mounted to deck;
- 50 mm diameter stress bar between temporary launch bearings;
- 4 x temporary launch bearings. Each bearing has two custom built-in 900 mm diameter pot bearings to accommodate deck rotation and construction tolerances of the sliding surfaces;
- 4 x roller side guides fixed to the temporary launch bearings; and
- 13mm thick Eberspächer sliding pads.






Transverse Launching

The launch designer has designed the launch according to the following basic criteria:

- Dead Weight of Bridge..... 4000t / Abutment
- Max Friction System can overcome 11.6%
- Maximum pulling capacity of system 4630kN / Abutment
- Pulling capacity of SLU 330t jack 3220kN / Abutment
- Expected starting force per increment 2400kN @ 6%
- Expected pulling force..... 1600kN @ 4%
- Max. safe force allowed before investigation required 3200kN @ 8%
- Capacity of system identical forward and reverse



Transverse Launching



Acknowledgements



| | |
|-----------------------------|--|
| Client: | Western Cape Government, Department of Transport & Public Works |
| Local Municipality: | Langeberg Municipality |
| Consulting Engineer: | AECOM SA |
| Bridge Engineering: | AECOM SA, AECOM UK & Edward Smuts |
| Erection Engineering: | AECOM SA & Dave Middleton (Interim Maintenance Contract & New Construction contract Contract) |
| Main contractors: | Basil Read (OCC), Haw & Inglis (IMC & NCC) |
| Specialist Sub-contractors: | Amsteele Systems & Redaelli Nova Engineering Works Fairbrother Geotechnical Engineering AllWeld |
| Temporary Works Designers: | Form Scaff & Richard Beneke Designs Aurecon, Maffeis, Nyeleti |









Thank You!

WESTERN CAPE GOVERNMENT

AECOM Imagine it.
Delivered.